

PROJECT:		BERLIN RESIDENCE												Subtotal		AMOUNT	
LOCATION:		86 2ND STREET												Over & Profit		\$18,237	
														Total		\$83,370	
SR	Dwg.	CSI NO	DESCRIPTION	QTY.	Waste	Qty w/ Waste	UNIT	UNIT LABOR COST	LAB HRS	MEN	RATE/HR	UNIT MATERIAL COST	TOTAL LABOR COST	TOTAL MATERIAL COST	TOTAL COST		
D10000 DIVISION 01 - GENERAL REQUIREMENTS																	
1			Mobilization	1	0%	1	LS	-				\$	-	\$	-		
2			Supervision	1	0%	1	LS	-				\$	-	\$	-		
3			Office overheads	1	0%	1	LS	-				\$	-	\$	-		
4	See Spec.		Temporary facilities and controls	1	0%	1	LS	-				\$	-	\$	-		
5			Temporary facilities and controls	1	0%	1	LS	-				\$	-	\$	-		
6			Project Closeouts	1	0%	1	LS	-				\$	-	\$	-		
7			Submittal and approval	1	0%	1	LS	-				\$	-	\$	-		
Subtotal														\$			
D00008 DIVISION 08 - OPENINGS																	
DOORS:																	
8	P.11		(3' Wide X 7' H) Exterior Door W/Frame	1	10%	1	EA	\$ 350.0	8.2	0.5	47.0	\$ 525.0	\$ 385.0	\$ 578	\$ 962.50	875	
9	P.11		(5' Wide X 7' H) Glass Door W/Wood Frame	1	10%	1	EA	\$ 460.0	10.8	0.7	47.0	\$ 690.0	\$ 506.0	\$ 759	\$ 1,265.00	1150	
10	P.15		(3' X 7') Pocket Wood Door	1	10%	1	EA	\$ 350.0	8.2	0.5	47.0	\$ 525.0	\$ 385.0	\$ 578	\$ 962.50	875	
11	P.15		(2'-10" X 7') Pocket Wood Door	1	10%	1	EA	\$ 340.0	8.0	0.5	47.0	\$ 510.0	\$ 374.0	\$ 561	\$ 935.00	850	
12	P.15		(2'-10" X 7') Wood Door W/Wood Frame	4	10%	4	EA	\$ 340.0	31.8	2.0	47.0	\$ 510.0	\$ 1,496.0	\$ 2,244	\$ 3,740.00	850	
13	P.15		(3' X 7') Double Closet Door	6	10%	7	EA	\$ 350.0	49.1	3.1	47.0	\$ 525.0	\$ 2,310.0	\$ 3,465	\$ 5,775.00	875	
14	P.15		(2'-4" Wide X 7' H) Wood Pocket Door	2	10%	2	EA	\$ 330.0	15.4	1.0	47.0	\$ 495.0	\$ 726.0	\$ 1,089	\$ 1,815.00	825	
15	P.19		(2'-4" Wide X 7' H) Wood Door W/Frame	1	10%	1	EA	\$ 340.0	8.0	0.5	47.0	\$ 510.0	\$ 374.0	\$ 561	\$ 935.00	850	
16	P.19		(5' Wide X 7' H) Double Wood Door W/Frame	1	10%	1	EA	\$ 460.0	10.8	0.7	47.0	\$ 690.0	\$ 506.0	\$ 759	\$ 1,265.00	1150	
17	P.7		(11'-6" Wide X 7' H) Bi-Fold Glazed Aluminum Door	1	10%	1	EA	\$ 1,440.0	33.9	2.1	47.0	\$ 2,173.5	\$ 1,593.9	\$ 2,391	\$ 3,984.75	3623	
18	P.7		(3' Wide X 7') Wood Door W/Wood Frame	1	10%	1	EA	\$ 350.0	8.2	0.5	47.0	\$ 525.0	\$ 385.0	\$ 578	\$ 962.50	875	
19	P.7		(4'-4" Wide X 7' H) Double Wood Door W/Frame	1	10%	1	EA	\$ 390.0	9.1	0.6	47.0	\$ 585.0	\$ 429.0	\$ 644	\$ 1,072.50	6975	
20	P.7		(3' X 7') Wood Door W/Wood Frame	5	10%	6	EA	\$ 340.0	39.8	2.5	47.0	\$ 510.0	\$ 1,870.0	\$ 2,805	\$ 4,675.00	850	
21	P.7		(3' Wide X 7' H) Wood Pocket Door W/Frame	1	10%	1	EA	\$ 340.0	8.0	0.5	47.0	\$ 510.0	\$ 374.0	\$ 561	\$ 935.00	850	
DOOR HARDWARES:																	
22	P.7,11,15,19		Door Hardware Set	27	10%	30	EA	\$ 66.0	41.7	2.6	47.0	\$ 99.0	\$ 1,960.2	\$ 2,940	\$ 4,900.50	165	
Subtotal														\$ 13,674		\$ 20,511	\$ 34,185
D00090 DIVISION 09 - FINISHES																	
CEILING:																	
23	P.7,11,15,19		(5/8" Thk) Gypsum Board Ceiling	84	10%	92	EA	\$ 53.6	105.4	6.6	47.0	\$ 80.4	\$ 4,951.8	\$ 7,428	\$ 12,379.62	134	
24	P.7,11,15,19		(5/8" Thk) Green Gypsum Board Ceiling	7	10%	8	EA	\$ 53.6	8.6	0.5	47.0	\$ 80.4	\$ 404.6	\$ 607	\$ 1,011.58	825	
25	P.7,11,15,19		(12" H) Gypsum Board Soffit	6	10%	6	EA	\$ 53.6	7.3	0.5	47.0	\$ 80.4	\$ 343.8	\$ 516	\$ 898.48	134	
26	P.7,11,15,19		Taping	970	10%	1,067	LF	\$ 0.5	10.9	0.7	47.0	\$ 0.7	\$ 512.2	\$ 788	\$ 1,280.40	1.2	
27	P.7,11,15,19		Mudding	165	10%	181	LBS	\$ 1.8	6.9	0.4	47.0	\$ 2.7	\$ 325.7	\$ 489	\$ 814.33	4.5	
28	P.7,11,15,19		Drywall Screws	4365	10%	4,802	EA	\$ 0.0	2.3	0.1	47.0	\$ 0.0	\$ 109.5	\$ 164	\$ 273.69	0.057	
PARTITION WALLS																	
29			(6" Thk) Exterior Wall	20			LF	\$				\$					
30	P.7,11,15,19		5/8" Gypsum Board On One Side - (4'x8')	6	10%	7	EA	\$				\$					
31	P.7,11,15,19		R-25 Batt Insulation	196	10%	216	SF	\$				\$					
32	P.7,11,15,19		2x8" Wood Studs - 10' H	15	10%	17	EA	\$				\$					
33	P.7,11,15,19		2x8" Top & Bottom plates	60	10%	66	LF	\$				\$					
34	P.7,11,15,19		Acoustical Sealant	46	10%	44	SF	\$				\$					
35			(8" Thk) Exterior Wall	13			EA	\$				\$					
36	P.7,11,15,19		5/8" Gypsum Board On One Side - (4'x8')	3	10%	4	EA	\$				\$					
37	P.7,11,15,19		R-25 Batt Insulation	106	10%	116	SF	\$				\$					
38	P.7,11,15,19		2x8" Wood Studs - 10' H	10	10%	11	EA	\$				\$					
39	P.7,11,15,19		2x8" Top & Bottom plates	38	10%	42	LF	\$				\$					
40	P.7,11,15,19		Acoustical Sealant	26	10%	28	LF	\$				\$					
41			(6" Thk) Exterior Wall	49			LF	\$				\$					
42	P.7,11,15,19		5/8" Gypsum Board On One Side - (4'x8')	10	10%	11	EA	\$				\$					
43	P.7,11,15,19		R-25 Batt Insulation	312	10%	343	SF	\$				\$					
44	P.7,11,15,19		2x8" Wood Studs - 10' H	32	10%	35	EA	\$				\$					
45	P.7,11,15,19		2x8" Top & Bottom plates	128	10%	141	LF	\$				\$					
46	P.7,11,15,19		Acoustical Sealant	85	10%	94	LF	\$				\$					
47			(6" Thk) Exterior Wall - (G.B.1)	7			LF	\$				\$					
48	P.7,11,15,19		5/8" Green Gypsum Board On One Side - (4'x8')	2	10%	2	EA	\$				\$					
49	P.7,11,15,19		R-25 Batt Insulation	59	10%	64	SF	\$				\$					
50	P.7,11,15,19		2x8" Wood Studs - 10' H	5	10%	6	EA	\$				\$					
51	P.7,11,15,19		2x8" Top & Bottom plates	21	10%	23	LF	\$				\$					
52	P.7,11,15,19		Acoustical Sealant	14	10%	16	LF	\$				\$					
53			(6" Thk) Exterior Wall	23			EA	\$				\$					
54	P.7,11,15,19		5/8" Gypsum Board On One Side - (4'x8')	7	10%	8	EA	\$				\$					
55	P.7,11,15,19		R-21 Batt Insulation	221	10%	243	SF	\$				\$					
56	P.7,11,15,19		2x6" Wood Studs - 10' H	17	10%	19	EA	\$				\$					
57	P.7,11,15,19		2x6" Top & Bottom plates	68	10%	74	LF	\$				\$					
58	P.7,11,15,19		Acoustical Sealant	45	10%	50	LF	\$				\$					
59			(6" Thk) Exterior Wall	11			LF	\$				\$					
60	P.7,11,15,19		5/8" Gypsum Board On One Side - (4'x8')	3	10%	3	EA	\$				\$					
61	P.7,11,15,19		R-21 Batt Insulation	93	10%	102	SF	\$				\$					
62	P.7,11,15,19		2x6" Wood Studs - 10' H	8	10%	9	EA	\$				\$					
63	P.7,11,15,19		2x6" Top & Bottom plates	34	10%	37	LF	\$				\$					
64	P.7,11,15,19		Acoustical Sealant	23	10%	25	LF	\$				\$					
65			(6" Thk) Exterior Wall (G.B.1)	11			EA	\$				\$					
66	P.7,11,15,19		5/8" Green Gypsum Board On One Side - (4'x8')	3	10%	3	EA	\$				\$					
67	P.7,11,15,19		R-21 Batt Insulation	93	10%	102	SF	\$				\$					
68	P.7,11,15,19		2x6" Wood Studs - 10' H	34	10%	37	EA	\$				\$					
69	P.7,11,15,19		2x6" Top & Bottom plates	34	10%	37	LF	\$				\$					
70	P.7,11,15,19		Acoustical Sealant	22	10%	25	LF	\$				\$					
71			(4" Thk) Interior Wall	8			EA	\$				\$					
72	P.7,11,15,19		5/8" Gypsum Board On Both Sides - (4'x8')	5	10%	6	EA	\$				\$					
73	P.7,11,15,19		2x4" Wood Studs - 10' H	7	10%	7	EA	\$				\$					
74	P.7,11,15,19		2x4" Top & Bottom plates	25	10%	27	LF	\$				\$					
75	P.7,11,15,19		Acoustical Sealant	33	10%	37	LF	\$				\$					
76			(4" Thk) Interior Wall	27			EA	\$				\$					
77	P.7,11,15,19		5/8" Gypsum Board On Both Sides - (4'x8')	12	10%	14	EA	\$				\$					
78	P.7,11,15,19		2x4" Wood Studs - 8' H	20	10%	23	EA	\$				\$					
79	P.7,11,15,19		2x4" Top & Bottom plates	82	10%	90	LF	\$				\$					
80	P.7,11,15,19		Acoustical Sealant	109	10%	120	LF	\$				\$					
81			(6" Thk) Interior Wall - (G.B.1)	16			LF	\$				\$					
82	P.7,11,15,19		5/8" Gypsum Board On One Side - (4'x8')	5	10%	6	EA	\$				\$					
83	P.7,11,15,19		5/8" Green Gypsum Board On One Side - (4'x8')	5	10%	6	EA	\$				\$					
84	P.7,11,15,19		2x6" Wood Studs - 10' H	12	10%	14	EA	\$				\$	</				

SF	Dwg.	CSI NO	DESCRIPTION	QTY.	Wastage	Qty w/ Waste	UNIT	UNIT LABOR COST	LAB HRS	MEN	RATE/HR	UNIT MATERIAL COST	TOTAL LABOR COST	TOTAL MATERIAL COST	TOTAL COST
112	P.7.11.15.19		2x6" Top & Bottom plates	20	10%	22	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
113	P.7.11.15.19		Acoustical Sealant	27	10%	29	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
114			(4" Thk) Interior Wall	2			LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
115	P.7.11.15.19		5/8" Gypsum Board On Both Sides - (4'x8')	1	10%	2	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
116	P.7.11.15.19		2x4" Wood Studs - 10' H	2	10%	2	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
117	P.7.11.15.19		2x4" Top & Bottom plates	7	10%	8	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
118	P.7.11.15.19		Acoustical Sealant	9	10%	10	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
119			(4" Thk) Interior Wall	54			LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
120	P.7.11.15.19		5/8" Gypsum Board On Both Sides - (4'x8')	28	10%	31	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
121	P.7.11.15.19		2x4" Wood Studs - 10' H	41	10%	45	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
122	P.7.11.15.19		2x4" Top & Bottom plates	162	10%	178	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
123	P.7.11.15.19		Acoustical Sealant	216	10%	237	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
124			(4" Thk) Wall Furring	4			LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
125	P.7.11.15.19		5/8" Gypsum Board On One Side - (4'x8')	2	10%	2	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
126	P.7.11.15.19		2x4" Wood Studs - 8' H	3	10%	3	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
127	P.7.11.15.19		2x4" Top & Bottom plates	12	10%	14	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
128	P.7.11.15.19		Acoustical Sealant	16	10%	18	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
129			(6" Thk) Wall Furring	6			LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
130	P.7.11.15.19		5/8" Gypsum Board On One Side - (4'x8')	3	10%	3	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
131	P.7.11.15.19		2x6" Wood Studs - 8' H	4	10%	5	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
132	P.7.11.15.19		2x6" Top & Bottom plates	17	10%	19	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
133	P.7.11.15.19		Acoustical Sealant	23	10%	25	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
134			(4" Thk) Interior Wall (G.B.1)	23			LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
135	P.7.11.15.19		5/8" Gypsum Board On One Side - (4'x8')	6	10%	6	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
136	P.7.11.15.19		5/8" Green Gypsum Board On One Side - (4'x8')	6	10%	6	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
137	P.7.11.15.19		2x4" Wood Studs - 10' H	17	10%	19	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
138	P.7.11.15.19		2x4" Top & Bottom plates	69	10%	76	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
139	P.7.11.15.19		Acoustical Sealant	92	10%	101	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
140			(2" Thk) Interior Wall	6			LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
141	P.7.11.15.19		5/8" Gypsum Board On Both Sides - (4'x8')	3	10%	4	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
142	P.7.11.15.19		2x2" Wood Studs - 10' H	4	10%	5	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
143	P.7.11.15.19		2x4" Top & Bottom plates	17	10%	18	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
144	P.7.11.15.19		Acoustical Sealant	22	10%	24	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
			Misc Items:												
145	P.7.11.15.19		5/8" Gypsum Board On Existing Wall Framing - (4'x8')	49	10%	54	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
146	P.7.11.15.19		5/8" Green Gypsum Board On Existing Wall Framing - (4'x8')	2	10%	3	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
147	P.7.11.15.19			2060	10%	2,266	LF	\$ 0.5	\$ 23.1	\$ 1.4	\$ 47.0	\$ 0.7	\$ 1,087.7	\$ 1,632	\$ 2,719.20
148	P.7.11.15.19		Mudding	349	10%	384	LES	\$ 1.8	\$ 14.7	\$ 0.9	\$ 47.0	\$ 2.7	\$ 991.8	\$ 1,038	\$ 1,729.41
149	P.7.11.15.19		Drywall Screws	9270	10%	10,197	EA	\$ 0.0	\$ 4.9	\$ 0.3	\$ 47.0	\$ 0.0	\$ 232.5	\$ 349	\$ 581.23
			TRIMS:												
150	P.7.11.15.19		4" Door Trim	684	10%	753	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
151	P.7.11.15.19		4" Window Trim	214	10%	235	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
			Subtotal									\$ 8,660	\$ 12,989	\$ 21,649	
		000012	DIVISION 12 - FURNISHINGS												
			COUNTERTOPS:												
152	P.7.11.15.19		(22" Wide) Wood Laminate Desk Countertop	17	10%	19	SF	\$ 12.8	\$ 5.1	\$ 0.3	\$ 47.0	\$ 19.2	\$ 237.5	\$ 356	\$ 593.71
153	P.7.11.15.19		(6' X 6'-8") Kitchen Stone Island Countertop	40	10%	44	SF	\$ 14.0	\$ 13.1	\$ 0.8	\$ 47.0	\$ 21.0	\$ 615.4	\$ 923	\$ 1,538.46
154	P.7.11.15.19		Kitchen Stone Countertop	101	10%	111	SF	\$ 14.0	\$ 33.1	\$ 2.1	\$ 47.0	\$ 21.0	\$ 1,536.9	\$ 2,335	\$ 3,892.35
155	P.7.11.15.19		(24" Wide) Stone Countertop	12	10%	13	SF	\$ 14.0	\$ 3.8	\$ 0.2	\$ 47.0	\$ 21.0	\$ 180.5	\$ 271	\$ 451.22
156	P.7.11.15.19		(18" Wide) Wood Vanity bench	6	10%	6	SF	\$ 12.0	\$ 1.6	\$ 0.1	\$ 47.0	\$ 18.0	\$ 76.4	\$ 115	\$ 191.07
157	P.7.11.15.19		(12" Wide) Wood Vanity bench	3	10%	3	SF	\$ 12.0	\$ 0.7	\$ 0.0	\$ 47.0	\$ 18.0	\$ 33.9	\$ 51	\$ 84.81
158	P.7.11.15.19		(24" Wide) Closet Countertop	7	10%	8	SF	\$ 12.0	\$ 2.0	\$ 0.1	\$ 47.0	\$ 18.0	\$ 96.1	\$ 144	\$ 240.24
159	P.7.11.15.19		(20" Wide) Bath Vanity Countertop	8	10%	9	SF	\$ 12.0	\$ 2.3	\$ 0.1	\$ 47.0	\$ 18.0	\$ 109.6	\$ 164	\$ 273.90
160	P.7.11.15.19		(20" Wide) Vanity Countertop	4	10%	5	SF	\$ 12.0	\$ 1.2	\$ 0.0	\$ 47.0	\$ 18.0	\$ 54.8	\$ 82	\$ 136.95
161	P.7.11.15.19		(2'-10" Wide) Stone Countertop	23	10%	25	SF	\$ 12.0	\$ 6.3	\$ 0.4	\$ 47.0	\$ 18.0	\$ 298.1	\$ 447	\$ 745.25
162	P.7.11.15.19		(6' H) White Oak Wood Veneer Millwork	35	10%	38	SF	\$ 12.0	\$ 9.8	\$ 0.6	\$ 47.0	\$ 18.0	\$ 460.2	\$ 690	\$ 1,150.38
			CABINETS:												
163	P.7.11.15.19		(22" Wide) Wood Laminate Drawer	6	10%	7	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
164	P.7.11.15.19		(6' X 6'-8") Kitchen Base Cabinets	1	10%	1	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
165	P.7.11.15.19		(24" Wide) Wood Veneer Lower Cabinets	16	10%	16	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
166	P.7.11.15.19		(12" Wide) Laminated Upper Cabinets	16	10%	17	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
167	P.7.11.15.19		(14" Wide X 20" H) Cushioned & Upholstered Top, Cupboards.	7	10%	8	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
168	P.7.11.15.19		(14" Wide) Base Laminated Cabinets	6	10%	6	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
169	P.7.11.15.19		(16" Wide) Plastic Laminated Base Cabinets	33	10%	36	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
170	P.7.11.15.19		(18" Wide) Wood Drawer	4	10%	4	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
171	P.7.11.15.19		(12" Wide) Wood Drawer	3	10%	3	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
172	P.7.11.15.19		(24" Wide) Closet Base Cabinets	4	10%	4	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
173	P.7.11.15.19		(20" Wide) Bath Base Cabinets	5	10%	6	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
174	P.7.11.15.19		(24" Wide) Kitchen Base Cabinets	19	10%	21	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
175	P.7.11.15.19		(14" Wide) Kitchen Wall Hung Laminated Cabinets	10	10%	11	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
176	P.7.11.15.19		(20" Wide) Vanity Laminated Base Cabinets	3	10%	3	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
177	P.7.11.15.19		(2'-10" Wide) Laminated Base Cabinets	8	10%	9	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
178	P.7.11.15.19		(14" Wide) Wood Laminated Wall Hung Cabinets	8	10%	9	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
179	P.7.11.15.19		(24" Wide) Wood Laminated Base Cabinets	12	10%	13	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
			SHELVING:												
180	P.7.11.15.19		(16" Wide) Open Shelving	7	10%	7	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
181	P.7.11.15.19		(2'-8" X 2'-1") Pantry Adjustable Shelving	1	10%	1	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
182	P.7.11.15.19		(3'-0" X 1'-10") Fridge Adjustable Shelving	1	10%	1	EA	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
183	P.7.11.15.19		(16" Wide) Kitchen bar Shelving	10	10%	11	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
184	P.7.11.15.19		(20" Wide) Closet Wire Shelving	6	10%	6	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
185	P.7.11.15.19		(16" Wide) 4-Layers Wire Closet Shelving	33	10%	36	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
186	P.7.11.15.19		(18" Wide) 4-Layers Closet Wire Shelving	12	10%	13	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
187	P.7.11.15.19		(24" Wide) 1-Layer Wood Shelving	6	10%	6	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
188	P.7.11.15.19		(14" Wide) 4-Layers Wood Laminated Shelving	6	10%	7	LF	\$ -	-	-	\$ -	\$ -	\$ -	\$ -	\$ -
			Subtotal									\$ 3,719	\$ 5,579	\$ 9,298	
			TOTAL AMOUNT												\$ 65,133
			OVERHEAD AND PROFIT (25%)				28%								\$ 18,237.11
			TOTAL BASE BID												\$ 83,370
			NOTES:												